



Norwalk IR Procedure Room List of Alternates as shown on Plans

ALL TRADES (Added by Addendum #1)

1. Existing Waiting & Office (Sheets A103, A104, M101, M200, E202, E300, FP101)
Additive Alternate: Renovating the existing waiting and office area just north of the Control Room.

Mechanical

1. FC-1 (Sheet M100 Note #4 & #9)
Deductive Alternate: Field verify condition and size of existing linesets. Linesets can remain and be reused if they are in fair or better condition and are of the proper size for use with new fan coil FC-1 per manufacturer's installation instructions.
2. CU-1 (Sheet M100 Note #5 & #10)
Deductive Alternate: Field verify condition and cooling size of existing fan coil unit. If the unit is minimum 3-tons and in fair or better condition, the existing fan coil unit can be relocated and reused. Extend existing controls, services and refrigerant piping to new location. Associated existing thermostat to be relocated. Existing condenser to remain and be reused. Coordinate ceiling grid with Architect to provide space for 37" x 37" unit grill installation.

Electrical

3. FC-1 (Sheet E100 Note #4 & E201 Note #18)
Deductive Alternate: Provide deduct if existing FC-1 is reused and relocated in place of new split system unit. Extend existing conduit and wiring of existing fan coil unit to new location. Coordinate all work with mechanical contractor.

Plumbing

4. FC-1 (Sheet P100 Note 12)
Deductive Alternate: If existing fan coil and condensate drain to remain and be reused.

Medical Gas

5. Alarm Device (Sheet P100 Note #2)
Deductive Alternate: Provide deduct to reuse area alarm devices and relocate sensors to new zone valve box locations.
6. Valve Box (Sheet P100 Note #3 & #9)
Deductive Alternate: Provide deduct to relocate and reuse existing medical gas valve box.