



DRAWING CONTENTS

C1 COVER SHEET
GN1 GENERAL NOTES
GN2 GENERAL NOTES

SECTION A

A1	EQUIPMENT LAYOUT
A2	EQUIPMENT ELEVATIONS

SECTION S

S1 STRUCTURAL LAYOUT
S2 STRUCTURAL DETAILS

SECTION E

E1	ELECTRICAL LAYOUT
E2	ELECTRICAL SCHEMATIC
E3	ELECTRICAL DETAILS
E4	CABLE LENGTH DIAGRAM (FOR INTERNAL USE ONLY)

TOSHIBA

Leading Innovation >>>

VA AUGUSTA TOGUS (AQUILION — ONE VISION) 1 VA CTR AUGUSTA, ME 04330				REV	DATE	REVISD SHEET(S)	INT
THESE TOSHIBA PLANS ARE FOR INFORMATIONAL PURPOSES ONLY AND SHALL NOT BE USED FOR ANY PURPOSE OTHER THAN THAT AGREED UPON BETWEEN TOSHIBA AND THE CUSTOMER. THESE SITE PLANS ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.					04-13-16	ORIGINAL FINAL DRAWING COMPLETED	M.P.P.
					05-12-16	A1, S1, E1 & E2.	G.O.
					07-06-16	A1, S1, E1 & E2.	G.O.
DATE: 07-06-16							
SCALE: NOT TO SCALE							
PLANNER: G.O.							
SID: 30007427							
PROJECT NO. 140014842CTF2							
C1							

GENERAL NOTES CUSTOMER / CONTRACTOR IS RESPONSIBLE FOR THE FOLLOWING UNLESS OTHERWISE NOTED. GENERAL A. TOSHIBA RESERVES THE RIGHT TO CHANGE THESE DESIGNS AND SPECIFICATIONS WITHOUT NOTICE. B. THE CUSTOMER/CONTRACTOR IS RESPONSIBLE TO ENSURE THAT ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES AND ORDINANCES ARE COMPLIED WITH. C. PRIOR TO EQUIPMENT DELIVERY AND INSTALLATION, THE SITE MUST BE 100% COMPLETE, CLEAN AND FREE OF DUST. CUSTOMER/CONTRACTOR AND TOSHIBA INSTALLATION PROJECT MANAGER MUST COMPLETE A SITE WALK THROUGH 1 WEEK PRIOR TO DELIVERY AND DETERMINE ACCEPTABILITY FOR DELIVERY. D. ANY CABINETRY THAT MAY BE REQUIRED TO HOUSE VIDEO RECORDERS, MONITORS, KEYBOARDS, OR OTHER ANCILLARY EQUIPMENT SHALL BE SUPPLIED AND INSTALLED BY CUSTOMER/CONTRACTOR. E. PROVIDE ADEQUATE VENTILATION WITHIN CABINETRY AND INSTALL AXIAL FANS ON THE TOP, SIDE, OR BACK OF CABINETS, IF REQUIRED. F. THESE TOSHIBA SITE PLANS DO NOT INDICATE EQUIPMENT REQUIREMENTS FOR ITEMS NOT SOLD BY TOSHIBA SUCH AS, PHYSIOLOGICAL MONITORS, LASER CAMERAS, INJECTORS, ETC. SPECIFICATIONS FOR THOSE ITEMS MUST BE OBTAINED FROM THE VENDOR AND INCLUDED IN THE DESIGN TOTALS. G. DESIGN, FABRICATE, AND INSTALL MEDICAL GAS PEDESTAL, IF REQUIRED. CONSULT WITH TOSHIBA INSTALLATION PROJECT MANAGER FOR SUITABLE LOCATIONS. H. CUSTOMER/CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AN OPERATING PHONE IN THE CONTROL ROOM AT THE TIME TOSHIBA EQUIPMENT INSTALLATION BEGINS. I. CUSTOMER/CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ADEQUATE LIGHTING FOR SERVICING OF EQUIPMENT IN ALL AREAS OF THE INSTALLATION. J. THE CUSTOMER/CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL COSTS REQUIRED FOR THE ENGINEERING AND/OR REMOVAL OF ANY HAZARDOUS MATERIALS SUCH AS ASBESTOS. K. CUSTOMER/CONTRACTOR SHALL SUPPLY AND INSTALL MATERIALS AND OTHER FEATURES SPECIFIED IN THE TOSHIBA SITE PLANS. CUSTOMER/CONTRACTOR SHALL SUPPLY AND INSTALL ALL COUNTERTOPS, SINKS, CASE WORK AND CABINETS SPECIFIED IN THE TOSHIBA SITE PLANS. PLUMBING L. PLUMBING IS NOT REQUIRED FOR THIS TOSHIBA EQUIPMENT. M. IT IS RECOMMENDED THAT A SINK BE PROVIDED FOR USE BY PERSONNEL. SITE CONDITIONS N. DIMENSIONS TO WALLS AND OR OTHER ROOM FEATURES, EXCEPT FOR NOTED COLUMN AND BEAM CENTER LINES SHALL BE FROM FINISHED SURFACES. O. CT GANTRY SHOULD NOT BE INSTALLED WITHIN 10 MAGNETIC GAUSS FIELD. P. THE WINDOW FOR MONITORING THE SCAN ROOM SHOULD BE IN FRONT OF OR ON THE SIDE OF THE CONSOLE DESK, THE LOWEST WINDOW FRAME SHOULD BE 36" ABOVE THE FLOOR FOR EASY PATIENT MONITORING. Q. A DOOR BETWEEN THE SCAN AND CONTROL ROOM IS RECOMMENDED. NETWORKING REQUIREMENTS R. NETWORK REQUIREMENTS WILL VARY BY SITE. TOSHIBA REPRESENTATIVE WILL REQUIRE DICOM DEVICE INFORMATION. ADDITIONAL I.P. ADDRESSES, AND I.T. DEPARTMENT CONTACT INFORMATION PRIOR TO INSTALLATION. TRANSPORT REQUIREMENTS S. EQUIPMENT INGRESS ROUTE MUST BE CHECKED PRIOR TO EQUIPMENT DELIVERY TO ENSURE THE LARGEST AND HEAVIEST ITEMS OF EQUIPMENT CAN BE ACCOMMODATED, PRIOR TO EQUIPMENT DELIVERY. DIMENSIONS OF DOORWAYS SHOULD BE NO LESS THAN 5'-0" CLEAR IN WIDTH. CONTACT THE TOSHIBA INSTALLATION PROJECT MANAGER FOR DETAILS PERTAINING TO THE LARGEST AND HEAVIEST COMPONENTS FOR THIS INSTALLATION (SEE DETAIL 2, SHEET GN2). 07-09-15		SPECIAL NOTES SPECIAL SEISMIC CERTIFICATION A. THE FOLLOWING COMPONENTS HAVE SPECIAL SEISMIC CERTIFICATION: A.A. OSP-0174-10 GANTRY AQUILION ONE VISION, AQUILION ONE 640, AQUILION ONE 320: CGGT-030A/1A AQUILION PRIME (TYPE D): CGGT-032A/2A AQUILION RXL: CGGT-018B/1A, CGGT-018B/2A PATIENT COUCH AQUILION ONE VISION, AQUILION ONE 640, AQUILION ONE 320: CBTB-032A/1A (EXTENDED), CBTB-032B/1A (COMPACT) LATERAL MOVEMENT UNIT: CALU-001A/3C (OPTIONAL) AQUILION PRIME (TYPE D): CBTB-032A/1A (EXTENDED), CBTB-032B/1A (COMPACT) LATERAL MOVEMENT UNIT: CALU-001A/3C (OPTIONAL) AQUILION RXL EXTENDED: CBTB-028A/1A, CBTB-032A/3A AQUILION RXL COMPACT: CBTB-028B/1A, CBTB-032B/3A POWER DISTRIBUTOR AQUILION ONE VISION, AQUILION ONE 640, AQUILION ONE 320: CETF-010A/1A AQUILION PRIME (TYPE D): CETF-006B/1A AQUILION RXL: CETF-006A/7A CPU & RECONSTRUCTION UNIT(S) AQUILION ONE VISION, AQUILION ONE 640, AQUILION ONE 320: CKCN-015B/5A AQUILION PRIME (TYPE D): CKCN-017A/2B AQUILION VELOCT: CKCN-016C/5A AQUILION RXL: CKCN-016B/4A LCD MONITORS KEYBOARDS MOUSE A.B. OSP-0119-10 G8000 UNINTERRUPTIBLE POWER SUPPLY - G8000 (AS APPLICABLE) AQUILION ONE VISION ONLY: 150kVA ALL OTHER CT MODELS: 100kVA A.C. OSP-0088-10 BAT - BC43 (PAIRED WITH G8000 UPS) (AS APPLICABLE) B. WEIGHTS SHOWN ON THE OSP DOCUMENTS ARE GENERALLY A MAXIMUM AND THE WEIGHTS SHOWN ON THESE SITE PLANS REFLECT THE EQUIPMENT AS ORDERED. 07-09-15		ELECTRICAL NOTES CUSTOMER / CONTRACTOR IS RESPONSIBLE FOR THE FOLLOWING UNLESS OTHERWISE NOTED. A. THESE SITE PLANS ARE INTENDED TO DEPICT ONLY A CONCEPT OF THE ELECTRICAL REQUIREMENTS FOR THE TOSHIBA EQUIPMENT. THE DESIGN OF ALL ELECTRICAL ELEMENTS MUST BE SPECIFIED BY A LICENSED ELECTRICAL ENGINEER IN ACCORDANCE WITH TOSHIBA SPECIFICATION AND ALL APPLICABLE CODES. B. IN ACCORDANCE WITH NEC ARTICLE 517-72(B), THE EQUIPMENT CIRCUIT BREAKER(S) MUST BE LOCATED SO THAT THEY SHALL BE OPERABLE FROM A LOCATION READILY ACCESSIBLE FROM THE CONTROL AREA. IF THIS IS IMPOSSIBLE OR IMPRACTICAL, THE USE OF A SHUNT TRIP TYPE BREAKER WILL BE NECESSARY TO SATISFY THIS REQUIREMENT. THE EMERGENCY OFF BUTTON FOR THE SHUNT TRIP SHOULD BE LOCATED IN THE CONTROL AREA. C. THE CUSTOMER/CONTRACTOR SHALL SUPPLY AND INSTALL ALL CIRCUIT BREAKERS, CONDUITS, JUNCTION BOXES, DUCTS, ETC. SPECIFIED HEREIN. D. THE TOSHIBA SITE PLANS DO NOT SPECIFY ELECTRICAL REQUIREMENTS FOR EQUIPMENT NOT SOLD BY TOSHIBA. THESE REQUIREMENTS MUST BE OBTAINED BY THE VENDOR. E. TOSHIBA WILL SUPPLY INTERCONNECTING CABLES FOR THE TOSHIBA EQUIPMENT. TOSHIBA WILL INSTALL IF LOCAL TRADE LABOR PERMITS. F. EXCEPT FOR THEIR USE IN POWER LINE CONNECTIONS TO EQUIPMENT CABINETS, FLEXIBLE CONDUIT SHALL NOT BE USED IN THIS INSTALLATION. ONLY FACTORY CONDUIT ELBOWS SHALL BE USED. G. DUCT WORK SHALL BE PROVIDED WITH SWEEP ELBOWS. H. ALL JUNCTION BOXES AND DUCTS THAT PENETRATE THE FLOOR SHALL BE WATERPROOF TYPE AND PROVIDED WITH GASKETED WATERPROOF COVERS. ALL FLOOR JUNCTION BOXES AND DUCT COVERS SHALL BE CAPABLE OF SUPPORTING A CONCENTRATED LOAD OF 200 LBS. I. GROMMETED OPENINGS ARE SHOWN FOR REFERENCE PURPOSES ONLY. VERIFY SIZE AND LOCATION WITH TOSHIBA REPRESENTATIVE. ALL GROMMETED OPENINGS SHALL HAVE NO SHARP EDGES. J. ALL CHASE & GROMMETED OPENINGS SHALL HAVE PLASTIC/NYLON BUSHINGS. K. ALL WALL DUCT WORK SHALL HAVE THE MINIMUM NUMBER OF COMPARTMENTS SPECIFIED IN THE ELECTRICAL DUCT LEGEND (SHEET E1). TRANSITIONS SUCH AS HORIZONTAL TO VERTICAL WALL DUCT OR WALL DUCT TO JUNCTION BOXES MUST BE REVIEWED ON AN INDIVIDUAL BASIS WITH THE INSTALLATION PROJECT MANAGER. LOCAL CODES MAY REQUIRE THE USE OF CROSS-OVER TUNNELS OR OTHER SUCH DEVICES TO MAINTAIN CABLE SEPARATION. L. ALL DUCT AND CONDUITS SHALL BE ELECTRICALLY BONDED AS A GROUNDING PATH IN ACCORDANCE WITH NEC ARTICLE 517-13(B). M. CUSTOMER/CONTRACTOR SHALL SUPPLY AND INSTALL GREENLEE NYLON MEASURING PULL STRING OR EQUIVALENT IN ALL CONDUITS AND CLOSED DUCT WORK. N. CONDUIT RUNS SHOWN ARE FOR REFERENCE ONLY. ALL CONDUIT RUNS MUST TAKE THE SHORTEST MOST DIRECT ROUTE POSSIBLE. O. CONDUIT RUNS MAY HAVE A MAXIMUM OF (3) 90° BENDS. P. 110VAC GROUNDED OUTLETS SHALL BE PROVIDED ON WALLS NEAR THE TOSHIBA EQUIPMENT FOR USE DURING EQUIPMENT SERVICE. Q. CUSTOMER/CONTRACTOR MUST SUPPLY AND INSTALL ALL INCOMING POWER CABLES FROM CIRCUIT BREAKER(S) TO TOSHIBA EQUIPMENT CONNECTION POINT. CABLE TYPE MUST BE MTW MULTI-STRAND COPPER - NO ALUMINUM IS PERMITTED. CABLE SIZE MUST BE IN ACCORDANCE WITH TOSHIBA POWER QUALITY REQUIREMENTS. (SEE SHEET E3). R. CUSTOMER/CONTRACTOR IS TO SUPPLY AND INSTALL ALL NECESSARY HARDWARE TO ENCLOSE INCOMING POWER CABLES IN FLEXIBLE WATER TIGHT CONDUIT FROM CIRCUIT BREAKER(S) TO TOSHIBA EQUIPMENT CABINET(S). S. ANY CHANGES IN THE LOCATION OR TYPE OF CONDUIT, DUCT WORK, JUNCTION BOXES, ETC. MUST BE SUBMITTED IN WRITING TO THE TOSHIBA INSTALLATION PROJECT MANAGER FOR APPROVAL. T. A SEPARATE CIRCUIT, FED FROM THE FACILITY RADIOLOGY PANEL OR A MAIN SERVICE PANEL IS REQUIRED. USE OF A SUB PANEL WITH LOADS SUCH AS ELEVATORS, HVAC, MOTORS, ETC. IS NOT PERMITTED. U. ALL DUCT WORK MAKING A 90° ANGLE MUST BE CHAMFERED FOR CABLE ACCESS. V. JUNCTION BOX SIZES SPECIFIED ON SHEET E1 MAY BE INCREASED AS NEEDED. W. FIBER OPTIC CABLES REQUIRE A MINIMUM RADIUS OF 4 1/2". DUCT WORK DESIGN MUST ACCOMMODATE THIS REQUIREMENT. 07-17-14		ELECTRICAL REQUIREMENTS FOR AQUILION SUPPLY CONFIGURATION: 3 PHASE DELTA OR WYE SUPPLY VOLTAGE: 480V, 150 AMP, 60 Hz DISTRIBUTION CAPACITY: 150 KVA 07-17-14 VIBRATION SPECIFICATION MAXIMUM VIBRATIONAL ACCELERATION DURING GANTRY ROTATION: 0.98 m/s² (0.1 G) OR LESS AT ALL FREQUENCIES MAXIMUM AMPLITUDE: 0.1 mm OR LESS IN ALL DIRECTIONS 04-07-15 CEILING HEIGHT RECOMMENDED CEILING HEIGHT: 9'-0" MINIMUM CEILING HEIGHT: 8'-2 1/2" 07-17-14 HVAC REQUIREMENTS CUSTOMER TO PROVIDE THE NECESSARY HVAC REQUIREMENTS FOR THE TOSHIBA EQUIPMENT TO OPERATE PROPERLY. AMBIENT TEMPERATURE SHOULD BE 68°-74° F WITH EQUIPMENT HEAT LOADS (SEE EQUIPMENT LEGEND SHEET A1) HUMIDITY RANGE OF 40-70% NON-CONDENSING A. STATED AMBIENT TEMPERATURE IS TO BE PROVIDED AND MAINTAINED AS SPECIFIED. ALL CALCULATIONS ARE TO UTILIZE TOSHIBA PROVIDED HEAT OUTPUT SPECIFICATIONS OF EQUIPMENT. B. A MINIMUM OF 10 AIR CHANGES PER HOUR IS SUGGESTED, CONSULT LOCAL CODE. C. AIR SUPPLY DUCTS SHOULD NOT BE PLACED DIRECTLY OVER EXAMINATION TABLES FOR PATIENT COMFORT. 07-17-14		DESCRIPTION INT M.M.P. G.O. G.O. 04-13-16 05-12-16 07-06-16 04-13-16 05-12-16 07-06-16 ORIGINAL FINAL DRAWING COMPLETED. NO CHANGES MADE TO THIS SHEET. NO CHANGES MADE TO THIS SHEET. 07-09-15</	
--	--	--	--	---	--	--	--	---	--

MINIMUM SITE REQUIREMENTS CHECKLIST

PROJECT:		SITE INSPECTION DATE:	
EQUIPMENT DELIVERY DATE:		INSPECTED BY:	
IN ORDER TO ENSURE A TIMELY AND SUCCESSFUL INSTALLATION, IT IS NECESSARY TO COMPLETE THIS FORM PRIOR TO INSTALLATION. PLEASE ASSIST TOSHIBA BY HAVING THE CONTRACTOR OR YOUR REPRESENTATIVE COMPLETE THE FOLLOWING:			
	1.	ALL WALLS, FLOORS, AND CEILINGS FINISHED. WALLS PAINTED, FLOORS TILED, AND CEILING GRID WORK AND FIXTURES INSTALLED.	
	2.	MONOLITHIC OR LAY-IN CEILING? PLEASE CIRCLE ONE.	
	3.	DOORS AND WINDOWS (INCLUDING ALL LEADED DOORS AND GLASS) INSTALLED AND LOCKABLE. DOORS TO BE REMOVED PRIOR TO DELIVERY BY CUSTOMER OR CONTRACTOR AND REINSTALLED AFTER EQUIPMENT MOVE-IN. RESERVE SECURE ROOM FOR STORAGE DURING INSTALLATION.	
	4.	AREA SET ASIDE FOR EQUIPMENT RIGGING AND MOVE-IN. ENVIRONMENTAL ISSUES ADDRESSED AND RESOLVED PRIOR TO EQUIPMENT DELIVERY (I.E. SURGICAL SUITE).	
	5.	EQUIPMENT (INGRESS) ROUTES ARE CLEAR AND OBSTACLE FREE.	
	6.	ALL CONDUIT, TROUGHING (WITH COVERS), AND BOXES INSTALLED (CLEAN AND DUST FREE). GROMMETED OPENINGS, CHASE NIPPLES, RACEWAY DIVIDERS, ETC. COMPLETE.	
	7.	CIRCUIT BREAKER INSTALLED AND INCOMING POWER (PER POWER QUALITY REQUIREMENTS) OPERATIONAL AND CONNECTED TO ROOM BREAKER(S).	
	8.	LOCATION OF ALL ELECTRICAL BREAKERS IN POWER CHAIN NOTED.	
	9.	ALL CONTRACTOR-INSTALLED STRUCTURAL SUPPORT DEVICES INSTALLED AND LEVELED ACCORDING TO T.A.M.S. SPECIFICATIONS ON SITE PLANS.	
	10.	ROOM LIGHTING INSTALLED AND OPERATIONAL.	
	11.	ENSURE THAT LIGHTING/SPRINKLER HEADS PRESENT NO CONFLICT WITH UNITS MOUNTED TO THE CEILING.	
	12.	ENSURE THAT NON-TOSHIBA SUPPLIED EQUIPMENT PRESENT NO CONFLICT WITH UNITS MOUNTED TO THE CEILING.	
	13.	110V ROOM OUTLETS OPERATIONAL.	
	14.	ALL CONTRACTOR-SUPPLIED CABLES PULLED AND TERMINATED, INCLUDING GROUND WIRE AND GROUND BUS BAR IN TROUGHING AS SPECIFIED IN THE TOSHIBA SITE PLANS.	
	15.	INTERFACE FOR DIMMING OF ROOM LIGHTS (IF APPLICABLE), WARNING LIGHTS AND DOOR SWITCHES INSTALLED AND INTERFACE AVAILABLE AND CONNECTED (RELAYS, ETC.).	
	16.	DUST-FREE ENVIRONMENT IN ALL RELATED ROOMS.	
	17.	HEATING AND AIR-CONDITIONING INSTALLED, OPERATIONAL, AND STABILIZED PER TOSHIBA SITE PLANS. FILTERS TO BE CHANGED 24 HOURS BEFORE DELIVERY.	
	18.	ALL MILLWORK COMPLETE AND INSTALLED.	
	19.	PLUMBING COMPLETED (INCLUDING GASES, IF APPLICABLE) ACCORDING TO TOSHIBA SPECIFICATIONS ON SITE PLANS.	
	20.	OPTIONAL COMPUTER FLOORING INSTALLED, IF APPLICABLE.	
	21.	THIRD PARTY VENDED ITEMS SUCH AS PROCESSORS, FILM CHANGERS, INJECTORS, GAS PEDESTALS, PHYSIOLOGICAL MONITORING EQUIPMENT, ETC., INSTALLED AND OPERATIONAL.	
	22.	TELEPHONE LINES (VOICE AND OPTIONAL MODEM) INSTALLED AND OPERATIONAL. A DEDICATED PHONE LINE IS REQUIRED FOR SITES THAT ARE RECEIVING INNERVISION.	
	23.	ALL UNFINISHED AREAS SEALED OFF TO PREVENT DUST CONTAMINATION.	
	24.	RECEPTACLE FOR TRASH AVAILABLE (LARGE ENOUGH FOR SHIPPING CRATES IF REQUIRED).	
	25.	SUB BASE PLATE(S) INSTALLED (IF REQUIRED).	
	26.	"PD" / "UPS" / "PCDU" INSTALLED AND OPERATIONAL (IF APPLICABLE).	
	27.	SEISMIC REQUIREMENTS, AND REQUIRED SEISMIC ANCHORING DEVICES INSTALLED (IF APPLICABLE).	
	28.	NETWORK CONNECTIONS INSTALLED AND OPERATIONAL.	
	29.	ALL APPLICABLE PERMITS OBTAINED.	


NOTICE:
CUSTOMER MUST COMPLETE ALL ITEMS ON THIS CHECKLIST BEFORE SCHEDULED DELIVERY DATE FOR THE EQUIPMENT. IF CUSTOMER FAILS TO DO SO, DELIVERY MAY BE DELAYED. FURTHERMORE, THE EQUIPMENT WARRANTY MAY BE VOIDED.

COMMENTS:

SIGNED TOSHIBA:

CONTRACTOR:

CUSTOMER:




- A. CEILING MOUNTED EQUIPMENT MUST BE POSITIONED TO AVOID INTERFERENCE WITH GANTRY.
- B. EQUIPMENT IS TO BE A MINIMUM OF 10" ABOVE THE RAISED GANTRY COVER (SEE DETAIL 1, SHEET A2).
- C. OVERHEAD COUNTERPOISE SYSTEMS CAN BE INSTALLED OVER GANTRY ISOCENTER IF THE PLATE IS MOUNTED AT A HEIGHT SUCH THAT THE BOTTOM OF THE POST DOES NOT INTERFERE WITH THE GANTRY (HEIGHT OF GANTRY + 10" CLEARANCE + POST LENGTH = MOUNTING PLATE HEIGHT ABOVE FINISHED FLOOR).

1 CEILING MOUNTED EQUIPMENT

SCALE: 1/2" = 1'-0"

07-17-14




MINIMUM DELIVERY REQUIREMENTS

RECOMMENDED HEIGHT OF ENTRY WAY DOORS: 7'-0"
RECOMMENDED WIDTH OF ENTRY WAY DOORS: 5'-0"
RECOMMENDED WIDTH OF CORRIDOR: 8'-0"

2 RECOMMENDED GANTRY DELIVERY REQUIREMENTS

SCALE: NOT TO SCALE

07-17-14



- A. CABINET SHOULD BE LIFTED FROM THE FRONT.
- B. CABINET SHOULD NOT BE LIFTED FROM THE SIDES.
- C. RECOMMENDED DOOR SIZE IS 60" CLEAR IN WIDTH.

3 UPS DELIVERY REQUIREMENTS

SCALE: NOT TO SCALE

07-17-14

VA AUGUSTA
TOGUS

(AQUILION – ONE VISION)

1 VA CTR
AUGUSTA, ME 04330

THESE TOSHIBA PLANS ARE FOR INFORMATIONAL PURPOSES ONLY AND SHALL NOT BE USED FOR ANY PURPOSE OTHER THAN THAT AGREED UPON BETWEEN TOSHIBA AND THE CUSTOMER. THESE SITE PLANS ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.

DATE: 07-06-16

SCALE: NOT TO SCALE

PLANNER: G.O.


SID: 30007427

PROJECT NO.
140014842CTF2



GN2

TOSHIBA
Leading Innovation >>>



FOR REFERENCE ONLY. NOT TO BE USED FOR CONSTRUCTION PURPOSES.



EQUIPMENT LAYOUT



SCATTER RADIATION FIELD



SCATTER RADIATION

UNITS: MICROGRAY (PER 100 mAs)

THE AMOUNT OF SCATTERED RADIATION DURING SCANNING IS SHOWN IN THE SCATTER RADIATION FIELD LAYOUT. REFER TO THIS DATA WHEN SCANNING TO MINIMIZE X-RAY EXPOSURE. NOTE THAT THE AMOUNT OF SCATTERED RADIATION DIFFERS DEPENDING ON THE PATIENT; THEREFORE, THE DATA SHOWN BELOW SHOULD BE USED ONLY AS A GUIDE.

120 kVp/100 mA/1.0 sec/M. FOV/0.5 mm X 80/320 mm PMMA PHANTOM

THE CUSTOMER/CONTRACTOR IS RESPONSIBLE FOR HAVING SHIELDING CALCULATIONS PREPARED BY A LICENSED RADIATION PHYSICIST.

THE ABOVE CALCULATION IS BASED ON A MULTI-SLICE EXPOSURE.

REVISED: 07-17-14

EQUIPMENT LEGEND

ITEM	ELEC. SYM.	ITEM DESCRIPTION SUPPLIED AND INSTALLED BY TOSHIBA	BTU/HR	WEIGHT	REF.
1	GANT	AQUILION GANTRY (TYPE A)	*	6,063	1 A2
2	PCH	AQUILION HIGH CAPACITY PATIENT COUCH (EXTENDED W/LATERAL MOVEMENT)	*	1,941	1 A2
3	NAVI	NAVI BOX	683	27	2 A2
4	MON	CONTROL MONITOR	192	18	3 A2
5	SPK1	SPEAKER (DESKTOP)	0	5	4 A2
6	SPK2	SPEAKER (WALL MOUNT)	0	5	4 A2
7	SKBD	KEYBOARD (SCAN)	0	6	-
8	DESK	DESK FOR MONITORS & KEYBOARDS	0	221	5 A2
9	CHR	CHAIR	0	55	-
10	INV	INNERVISION WORKSTATION	444	17	6 A2
11	CONB	AQUILION CONSOLE BOX	10,246	915	7 A2
12	PR	PHANTOM RACK (MOBILE CART TO TRANSPORT PHANTOMS)	0	287	9 A2
ITEM	ELEC. SYM.	ITEM DESCRIPTION - SUPPLIED BY TOSHIBA & INSTALLED BY CUSTOMER / CONTRACTOR	BTU/HR	WEIGHT	REF.
13	PD	POWER DISTRIBUTOR	4,777	1,654	8 A2
ITEM	ELEC. SYM.	OPTIONAL ITEM DESCRIPTION - SUPPLIED & INSTALLED BY TOSHIBA	BTU/HR	WEIGHT	REF.
14	VIT	VITREA WORKSTATION	4,144	73	-
15	FPMC	CT FLUOROSCOPY FLAT PANEL MONITOR (CEILING MOUNTED)	137	56	-
16	EOP	CT FLUOROSCOPY EXTENSION OPERATING PANEL (PEDESTAL MOUNTED)	0	T.B.D.	-
17	RWT	ECG MONITOR, R-WAVE TRIGGER (MODEL 7800)	-	6	-
18	INJ	MEDRAD INJECTOR (CEILING MOUNTED)	0	153	-
19	INJC	MEDRAD INJECTOR BASE UNIT	320	14	-
20	INJR	MEDRAD INJECTOR DISPLAY CONTROL UNIT W/STAND	0	9	-
21	DKBD	KEYBOARD (DISPLAY)	0	6	-
ITEM	ELEC. SYM.	OPTIONAL ITEM DESCRIPTION - SUPPLIED BY TOSHIBA & INSTALLED BY CUSTOMER / CONTRACTOR	BTU/HR	WEIGHT	REF.
22	UPS	G8000 150 KVA UNINTERRUPTIBLE POWER SUPPLY	11,118	2,557	10 A2
23	RSAP	REMOTE STATUS ALARM PANEL FOR "UPS"	-	10	11 A2
24	BAT	BATTERY CABINET FOR "UPS" (16 MINUTE) (BC43)	SEE DETAIL	3,548	12 A2
25	PICM	PDU INRUSH CURRENT MONITOR	-	35	13 A2

* AQUILION GANTRY & COUCH BTU / HOUR:

EXAM ROOM SCANNING 2 PATIENTS:	20,712 BTU/HR
EXAM ROOM SCANNING 3 PATIENTS:	21,991 BTU/HR
EXAM ROOM SCANNING 4 PATIENTS:	23,271 BTU/HR
EXAM ROOM SCANNING 5 PATIENTS:	24,550 BTU/HR
EXAM ROOM SCANNING MAXIMUM:	25,830 BTU/HR

FUTURE GROWTH OF FACILITY MUST BE CONSIDERED WHEN FORECASTING PATIENT NUMBERS FOR A/C REQUIREMENTS.

REVISED: 07-17-14

SITE PLAN APPROVAL

IN ORDER TO USE THIS SET OF FINAL SITE PLANS, A CUSTOMER SIGNATURE IS REQUIRED BELOW. THE CUSTOMER'S SIGNATURE DEMONSTRATES ACCEPTANCE OF THE LAYOUT SHOWN AND ALL STATED SPECIFICATIONS.

CUSTOMER: DATE:

SALES: DATE:

I.P.M.: DATE:

TOSHIBA

Leading Innovation >>>

INT	DESCRIPTION	M.M.P.	G.O.						
	ORIGINAL FINAL DRAWING COMPLETED.								
	UPDATED EQUIP. ROOM, ADDED "INJP", "INJC" & "INJR".								
	MOVED EQUIP. ADDED "DKBD", UPDATED "RWT" & "INJ".								

VA AUGUSTA TOGUS

(AQUILION - ONE VISION)

1 VA CTR
AUGUSTA, ME 04330

THESE TOSHIBA PLANS ARE FOR INFORMATIONAL PURPOSES ONLY AND SHALL NOT BE USED FOR ANY PURPOSE OTHER THAN THAT AGREED UPON BETWEEN TOSHIBA AND THE CUSTOMER. THESE SITE PLANS ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.

DATE: 07-06-16

SCALE: 1/4" = 1'-0"


PLANNER: G.O.

SID: 30007427


PROJECT NO.
140014842CTF2

A1

FOR REFERENCE ONLY. NOT TO BE USED FOR CONSTRUCTION PURPOSES.




STRUCTURAL LAYOUT



NOTE:
ANY FLOOR COVERING SHOULD BE REMOVED WITHIN THE AREA SHOWN IN DETAIL 1 EXPOSING CONCRETE PRIOR TO POURING THE EPOXY PAD. THE AREA FROM WHICH THE FLOOR COVERING HAS BEEN REMOVED MUST BE CLEAN AND FREE OF RESIDUE.

STRUCTURAL LEGEND		
ITEM	ITEM DESCRIPTION SUPPLIED AND INSTALLED BY TOSHIBA	REF.
A	BASE LAYOUT FOR AQUILION	1 S1
B	BASE LAYOUT FOR POWER DISTRIBUTOR	5&6 S2
ITEM	ITEM DESCRIPTION SUPPLIED BY MANUFACTURER AND INSTALLED BY CUSTOMER / CONTRACTOR	REF.
C	MOUNTING PLATE FOR CEILING MOUNTED CT FLUOROSCOPY	7 S2
D	MOUNTING PLATE FOR CEILING MOUNTED INJECTOR	2 S2
ITEM	ITEM DESCRIPTION SUPPLIED AND INSTALLED BY CUSTOMER / CONTRACTOR	REF.
E	MOUNTING PLATE FOR PDU INRUSH CURRENT MONITOR	8 S2



AN EPOXY PAD MUST BE POURED TO PROVIDE A LEVEL SURFACE. AN EPOXY PAD KIT WILL BE PROVIDED WITH THE PRE-INSTALLATION MATERIALS. CONTACT YOUR INSTALLATION PROJECT MANAGER FOR ADDITIONAL INFORMATION.

APPLY EPOXY RESIN TO THE AREA INDICATED ABOVE.

(I) EPOXY RESIN: SPECIFIC GRAVITY 1.2
HARDENER: SPECIFIC GRAVITY 1.2
MIXTURE RATIO: PER MANUFACTURER'S SPECIFICATIONS
CURING TIME: 36-48 HOURS (AT AN AMBIENT TEMPERATURE OF APPROXIMATELY 75°F)


(II) SINCE THE EPOXY RESIN TAKES 36-48 HOURS (DEPENDING ON AMBIENT TEMPERATURE) TO CURE, THIS WORK MUST BE COMPLETED BEFORE THE SYSTEM IS TO BE CARRIED IN.

(III) THE ACCURACY OF THE DIMENSIONS INDICATED IN THE ABOVE FIGURE MUST BE WITHIN THE RANGE OF $\pm 1/4"$ AS MEASURED WITH A TAPE MEASURE.

1 BASE EPOXY DETAIL HIGH CAPACITY + LATERAL

SCALE: 1/2" = 1'-0"

07-29-15



NOTES:
(I) MOUNTING PLATE SUPPLIED BY MANUFACTURER.
(II) INSTALL PER ENGINEER OF RECORD.
(III) MOUNTING HARDWARE SUPPLIED BY CUSTOMER CONTRACTOR.
(IV) FACILITIES REQUIRING SPECIAL SEISMIC CERTIFICATION MUST UTILIZE ANCHOR LOCATIONS SPECIFIED ON TOSHIBA PROVIDED SEISMIC CALCULATIONS.

2 CEILING MOUNTED INJECTOR PLATE DETAIL

SCALE: 2" = 1'-0"

01-26-16

TOSHIBA

Leading Innovation >>>

REV	DATE	DESCRIPTION	INT
04-13-16	04-13-16	ORIGINAL FINAL DRAWING COMPLETED.	M.M.P.
05-12-16	05-12-16	UPDATED EQUIPMENT ROOM & MOVED ITEM "D".	G.O.
07-06-16	07-06-16	ADDED ITEM "D".	G.O.

VA AUGUSTA
TOGUS

(AQUILION - ONE VISION)

1 VA CTR
AUGUSTA, ME 04330

THESE TOSHIBA PLANS ARE FOR INFORMATIONAL PURPOSES ONLY AND SHALL NOT BE USED FOR ANY PURPOSE OTHER THAN THAT AGREED UPON BETWEEN TOSHIBA AND THE CUSTOMER. THESE SITE PLANS ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.

DATE: 07-06-16

SCALE: 1/4" = 1'-0"


PLANNER: G.O.

SID: 30007427


PROJECT NO.
140014842CTF2

S1

THIS SHEET IS PART OF A SET OF DRAWING DOCUMENTS AS LISTED ON SHEET C1 AND SHOULD NOT BE SEPARATED.




1 GANTRY BASE (SLAB ON GRADE) ANCHOR BOLT DETAIL
SCALE: 1/2" = 1'-0"
04-07-15




- A. THE POWER DISTRIBUTOR MUST BE ANCHORED. THE STRUCTURAL ENGINEER OF RECORD IS TO DETERMINE THE APPROPRIATE METHOD.
- B. FOUR ANCHORS REQUIRED WHEN ANCHORING.
- C. IF UTILIZING TOSHIBA PROVIDED M12 ANCHORS: MINIMUM EMBEDMENT INTO CONCRETE: 3" (74 mm). DRILL 18 mm DIAMETER HOLES.

5 POWER DISTRIBUTOR (SLAB ON GRADE) ANCHOR BOLT DETAIL
SCALE: 1/2" = 1'-0"
05-13-15




2 GANTRY BASE (UPPER FLOOR) THRU BOLT DETAIL
SCALE: 1/2" = 1'-0"
04-07-15




- A. THE POWER DISTRIBUTOR MUST BE ANCHORED. THE STRUCTURAL ENGINEER OF RECORD IS TO DETERMINE THE APPROPRIATE METHOD.
- B. FOUR ANCHORS REQUIRED WHEN ANCHORING.
- C. IF UTILIZING TOSHIBA PROVIDED M12 ANCHORS: MINIMUM EMBEDMENT INTO CONCRETE: 3" (74 mm). DRILL 18 mm DIAMETER HOLES.


6 POWER DISTRIBUTOR (UPPER FLOOR) THRU BOLT DETAIL
SCALE: 1/2" = 1'-0"
05-13-15




3 TABLE BASE (SLAB ON GRADE) ANCHOR BOLT DETAIL
SCALE: 1/2" = 1'-0"
07-29-15



7 CEILING MOUNTED "FPMC" PLATE DETAIL
SCALE: 3" = 1'-0"
01-26-16



4 TABLE BASE (UPPER FLOOR) THRU BOLT DETAIL
SCALE: 1/2" = 1'-0"
03-11-16



8 WALL MOUNTED "PICM" PLATE DETAIL
SCALE: 1" = 1'-0"
08-26-15

TOSHIBA

Leading Innovation >>>

VA AUGUSTA TOGUS

(AQUILION — ONE VISION)

1 VA CTR
AUGUSTA, ME 04330

DATE: 07-06-16

SCALE: AS NOTED

PLANNER: G.O.

SID: 30007427

PROJECT NO.
140014842CTF2

S2


THIS SHEET IS PART OF A SET OF DRAWING DOCUMENTS AS LISTED ON SHEET C1 AND SHOULD NOT BE SEPARATED.



ELECTRICAL DUCT LEGEND		
ITEM	ITEM DESCRIPTION SUPPLIED AND INSTALLED BY CUSTOMER / CONTRACTOR	REF.
WD1	10" W X 3 1/2" D FLUSH/SURFACE MOUNTED WALL DUCT, W/(3) EQUALLY PARTITIONED COMPARTMENTS THROUGHOUT & REMOVABLE ACCESS COVERS. MOUNTED 12" A.F.F. TO BOTTOM OF DUCT.	5 E3
WD2	10" W X 3 1/2" D FLUSH/SURFACE MOUNTED WALL DUCT, W/(3) EQUALLY PARTITIONED COMPARTMENTS THROUGHOUT & REMOVABLE ACCESS COVERS. MOUNTED 12" A.F.F. TO BOTTOM OF DUCT.	5 E3

VA AUGUSTA TOGUS (AQUILION — ONE VISION) 1 VA CTR AUGUSTA, ME 04330	THESE TOSHIBA PLANS ARE FOR INFORMATIONAL PURPOSES ONLY AND SHALL NOT BE USED FOR ANY PURPOSE OTHER THAN THAT AGREED UPON BETWEEN TOSHIBA AND THE CUSTOMER. THESE SITE PLANS ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.
DATE:	07-06-16
SCALE:	1/4" = 1'-0"
PLANNER:	G.O.
SID:	30007427
PROJECT NO.	140014842CTF2
E1	



FOR REFERENCE ONLY. NOT TO BE USED FOR CONSTRUCTION PURPOSES.




NOTE:
FOR ABOVE CONNECTIONS, SEE DETAIL 2, SHEET E3.

FOR CONNECTIONS BETWEEN "UPS" & "BAT", SEE DETAIL 6,
SHEET E3.

ALL CABLES AND CONDUITS REQUIRED ARE TO BE PROVIDED BY
CUSTOMER CONTRACTOR.



ELECTRICAL SCHEMATIC
(PROVIDED FOR REFERENCE PURPOSES ONLY)



CABLE KEY	
	IN/UNDER FLOOR
	OVER CEILING
	CONTRACTOR DETERMINED

CONDUIT SCHEDULE

CONTRACTOR CONDUIT REFERENCE						CABLE REFERENCE				
Run No.	Conduit (Point to Point)		Conduit (Routing)	Conduit (Diameter)	Conduit (Max Length)	Cable (Point to Point)		Cable Length (Usable)	Cables (Supplied By)	
1	PD	GANT	UNDER FLOOR	(2) 2 1/2"	60'-0"	PD	GANT	SEE RUN "B" DETAIL (1/E4)	TOSHIBA	
2	PD	CONB	UNDER FLOOR	2 1/2"	63'-0"	PD	CONB	SEE RUN "C" DETAIL (1/E4)	TOSHIBA	
3	CONB	GANT	UNDER FLOOR	2"	60'-0"	CONB	GANT	SEE RUN "D" DETAIL (1/E4)	TOSHIBA	
4	CONB	GANT	UNDER FLOOR	(2) 3"	60'-0"	CONB	GANT	SEE RUN "E" DETAIL (1/E4)	TOSHIBA	
5	CONB	GANT	UNDER FLOOR	2"	60'-0"	CONB	GANT	SEE RUN "F" DETAIL (1/E4)	TOSHIBA	
6	GANT	JB	UNDER FLOOR	1"	57'-0"	GANT	INV	SEE RUN "J" DETAIL (1/E4)	TOSHIBA	
7	CONB	JB	UNDER FLOOR	1"	60'-0"	CONB	INV	SEE RUN "K" DETAIL (1/E4)	TOSHIBA	
8	CONB	JB	UNDER FLOOR	3"	60'-0"	CONB	NAVI	SEE RUN "G" DETAIL (1/E4)	TOSHIBA	
9	CONB	JB	UNDER FLOOR	1/2"	19'-0"	CONB	SPK1	SEE RUN "H" DETAIL (1/E4)	TOSHIBA	
10	CONB	SPK2	UNDER FLOOR	1/2"	30'-0"	CONB	SPK2	SEE RUN "I" DETAIL (1/E4)	TOSHIBA	
11	WL	GANT	CONTRACTOR DETERMINED	PER MANUFACTURER	PER MANUFACTURER	WL	GANT	PER MANUFACTURER	CONTRACTOR	
12	FPMC	CONB	OVER CEILING	2"	41'-0"	FPMC	CONB	50'-0" (SIGNAL)	TOSHIBA	
13	INJ	JB	OVER CEILING	2 1/2"	40'-0"	INJ	INJR	50'-0" (SIGNAL)	MANUFACTURER	

NOTE:
A. CONDUITS SUPPLIED/INSTALLED BY CUSTOMER/CONTRACTOR.
B. ALL CONDUIT RUNS MUST TAKE THE SHORTEST MOST DIRECT ROUTE POSSIBLE.
C. CONDUIT IS NOT TO BE RUN IN SUCH A MANNER THAT WILL EXCEED CONDUIT MAXIMUM LENGTH AS SHOWN IN THE SCHEDULES.

**VA AUGUSTA
TOGUS**

(AQUILION – ONE VISION)

1 VA CTR
AUGUSTA, ME 04330

THESE TOSHIBA PLANS ARE FOR INFORMATIONAL PURPOSES ONLY AND SHALL NOT BE USED FOR ANY PURPOSE OTHER THAN THAT AGREED UPON BETWEEN TOSHIBA AND THE CUSTOMER. THESE SITE PLANS ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.

DATE: 07-06-16

SCALE: 1/4" = 1'-0"

PLANNER: G.O.

SID: 30007427

PROJECT NO.
140014842CTF2

E2

TOSHIBA


Leading Innovation >>>

FOR REFERENCE ONLY. NOT TO BE USED FOR CONSTRUCTION PURPOSES.

POWER QUALITY REQUIREMENTS AQUILION		
SUPPLY CONFIGURATION:	3 PHASE, DELTA OR WYE (SEE NOTE A)	
NOMINAL LINE VOLTAGE:	480 VAC, 60 HZ (SEE NOTE B)	
LINE VOLTAGE VARIATION:	±10% STEADY-STATE INCLUDING SAGS AND SURGES	
LINE VOLTAGE BALANCE:	2% MAXIMUM OF NOMINAL VOLTAGE BETWEEN PHASES.	
FREQUENCY VARIATION:	±1 HZ	
HARMONIC DISTORTION:	3% STEADY-STATE, 5% FOR SHORT PERIODS (1 MINUTE OR LESS)	
GROUND CONDUCTOR IMPEDANCE:	0.1 OHMS @ 60 HZ, TO NEUTRAL-GROUND BONDING POINT (SEE NOTE D)	
STANDARD TRANSFORMER CAPACITY:	150 KVA	
MAXIMUM SYSTEM DEMAND:	125 KVA (IMAGING)	
CONDUCTOR SIZES (SEE NOTE E) FOR 1.5% IMPEDANCE OF BRANCH CONDUCTORS (20°C)		
CONDUCTOR SIZE	LENGTH	BREAKER FRAME SIZE
1/0 AWG	377 FT.	200 A
2/0 AWG	444 FT.	200 A
CIRCUIT BREAKER SIZE: (SEE NOTE F)	150 A	
MOMENTARY MAXIMUM CURRENT:	163 A	
MAXIMUM VOLTAGE DROP:	24.0 V	
% REGULATION:	5.0%	

STANDARD POWER QUALITY NOTES


- A. A GROUNDED NEUTRAL POWER SOURCE IS REQUIRED TO ASSURE RELIABLE EQUIPMENT OPERATION. THE NEUTRAL CONDUCTOR MAY NOT BE USED FOR A PARTICULAR SYSTEM.
- B. IN CASES WHERE MULTIPLE VOLTAGES ARE PERMITTED, THE PREFERRED SYSTEM VOLTAGE IS SPECIFIED.
- C. DUE TO THE HIGH INSTANTANEOUS POWER OF MEDICAL IMAGING SYSTEMS, USE THE HIGHEST AVAILABLE VOLTAGE SOURCE. ENSURE THAT LOWER VOLTAGE SOURCES ARE DERIVED DIRECTLY FROM THE SERVICE ENTRANCE OF THE FACILITY.
- D. GROUND CONDUCTORS ARE REQUIRED TO BE THE SAME SIZE AS THE PHASE CONDUCTORS UNLESS A LARGER SIZE IS REQUIRED BY CODE.
- E. ALL FEEDER AND BRANCH CIRCUIT CONDUCTORS MUST BE COPPER – ALUMINUM IS NOT PERMITTED.
- F. IF THE EQUIPMENT CIRCUIT BREAKER IS NOT LOCATED IN THE CONTROL AREA, A SHUNT TRIP BREAKER MUST BE USED IN ORDER TO COMPLY WITH N.E.C. 517-72(B). A PUSH-BUTTON TO OPERATE THE SHUNT TRIP MUST BE LOCATED IN THE CONTROL AREA.
- G. A SEPARATE CIRCUIT, FED FROM THE FACILITY RADIOLOGY PANEL OR A MAIN SERVICE PANEL IS REQUIRED. USE OF A SUB PANEL WITH LOADS SUCH AS ELEVATORS, HVAC, MOTORS, ETC., IS NOT PERMITTED.
- H. DEVICES SUCH AS UNINTERRUPTIBLE POWER SUPPLIES, POWER CONDITIONERS, VOLTAGE REGULATORS, AND FILTERS MAY BE INCOMPATIBLE WITH THIS IMAGING EQUIPMENT. CONSULT YOUR TOSHIBA SERVICE REPRESENTATIVE PRIOR TO PURCHASING OR INSTALLING THESE DEVICES.
- I. THE MAINS POWER GROUND CONDUCTOR IS TO BE RUN WITH THE POWER PHASE CONDUCTORS. THE GROUNDS TO BUILDING STEEL OR EARTH GROUND ARE NOT TO BE RUN WITH THE PHASE CONDUCTORS.



1 POWER REQUIREMENTS

SCALE: NOT TO SCALE


07-29-15



2 "CB" / "UPS" + "PD" WIRING DETAIL

SCALE: NOT TO SCALE


01-26-16



5 TYPICAL DUCT DETAIL WITH WALL DUCT & J-BOX

SCALE: NOT TO SCALE


07-17-14



3 WARNING LIGHT DETAIL

SCALE: NOT TO SCALE


07-17-14



6 UPS / BAT WIRING DETAIL

SCALE: NOT TO SCALE

07-17-14



4 TYPICAL "PD" J-BOX MOUNTING

SCALE: 1/2" = 1'-0"

07-17-14

TOSHIBA

Leading Innovation >>>

REV	DATE	DESCRIPTION	INT	M.I.P.	G.O.	G.O.
Δ	04-13-16	ORIGINAL FINAL DRAWING COMPLETED.				
Δ	05-12-16	NO CHANGES MADE TO THIS SHEET.				
Δ	07-06-16	NO CHANGES MADE TO THIS SHEET.				

VA AUGUSTA TOGUS

(AQUILION – ONE VISION)

1 VA CTR
AUGUSTA, ME 04330

THESE TOSHIBA PLANS ARE FOR INFORMATIONAL PURPOSES ONLY AND SHALL NOT BE USED FOR ANY PURPOSE OTHER THAN THAT AGREED UPON BETWEEN TOSHIBA AND THE CUSTOMER. THESE SITE PLANS ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.

DATE: 07-06-16

SCALE: NOT TO SCALE

PLANNER: G.O.

SID: 30007427

PROJECT NO.
140014842CTF2

E3

FOR REFERENCE ONLY. NOT TO BE USED FOR CONSTRUCTION PURPOSES.

THIS SHEET IS PART OF A SET OF DRAWING DOCUMENTS AS LISTED ON SHEET C1 AND SHOULD NOT BE SEPARATED.

